

QM15TB-H

Darlington Three-Phase Bridge

Various

Isolated Case (Y/N)=Yes

Circuits Per Package=1

V(BR)CEO (V)=600

V(BR)CBO (V)=600

I(C) Abs. (A) Collector Current=15

Absolute Max. Power Diss. (W)=100

h(FE) Min. Static Current Gain=50

@I(C) (A) (Test Condition)=15

@VCE (test)=2.0

V(CE)sat Max. (V)=2.0

@I(C) (A) (Test Condition)=15

t(r) Max. (s) Rise time=1.5u

t(f) Max. (s) Fall time.=11u

Package=Module-q